GEOINVEST ITZ
geotehnička rešenja

GEOINVEST ITZ d.o.o.
Vojvođanska 130A
11271 Surčin
PIB:110791329
MB:21387193

T: +381 11 428 38 15
M:+381 69 61 91 51
E: info@geoinvest.rs
t.r.: 170-30038928000-81
UniCradit banka a.d

Offer no. 011-3-22
for execution of geotechnical works on project
„Railway line: Belgrade - Subotica - State Border (Kelebia)
Section of Railway line Novi Sad - Subotica - State Border (Kelebija)

Client: „CHINA CIVIL ENGINEERING CONSTRUCTION CORPORATION"
Mr. Yu Jin

email: xiongsaitieluyifenbu@gmail.com

Surčin 20.12.2022.

Offer no. 011-3-22
for execution of geotechnical works on project
„Railway line: Belgrade - Subotica - State Border (Kelebia)
Section of Railway line Novi Sad - Subotica - State Border (Kelebija)

Bridge at km 101+980.62

Item and description	Quantity	Unit price (€)	Total (€)
1.0. General expenses			
1.1. General transport of equipment for drilling piles Ø 1200 mm, mobilization and demobilization at the location of the works and transfer to the other bank of the river (from S1 to S2)			12.000,00 €
			12.000,00 €
2.0. Piles Ø 1200 mm			
2.1. Drilling-excavation of piles with capping, installations of supplied material fco drill holes and move from pile to pile in one standing position.			
- pile diameter: 1,20 m - length: 17,0 m - total: 12 pcs.	204,00 m	125,00 €/m	25.500,00 €
2.2. Blind drilling is only counted if more than one meter is drilled. The first meter of blind drilling is not counted.	0,00 m	106,00 €/m	0,00 €
			25.500,00 €
		TOTAL:	**37.500,00 €**

NOTES:

1.Obligations of the contractor:

- ensure all geodetic measurements;
- fence the construction site (if necessary)
- obtain all necessary materials for installation (concrete, reinforcement cage, mixer + car pump);
- obtain reinforcement certificates and concrete sampling;
- finish the concrete top of the pile, trimming (concrete trimming)
- carry out the removal of excavated material;
- obtain all the necessary licences for the performance of the works;
- prepare appropriate working plateau dimension 15.00 x 10.00 m, measured from the axis of the pilot, with sufficient load-bearing capacity
- provide expert supervision
- provide access to the machines at all working positions, if access is not enabled, downtime is charged at 1000 eur/day.
- remove all underground installations in the work area;
- ensure continuous work, downtime longer than two hours of waiting time will be calculated if the subcontractor does not agree with the previously announced downtime;
- organize a guard service outside working hours;
- provide water supply to head of pile in case of need to maintain hydrostatic pressure in piles (liquid sand);

2. The calculation of the works will be carried out on the basis of the actually executed works verified through the building log and the building book, and according to the unit prices from the offer.

3. Offer validity - 7 days.

4. Method of payment: 20 % avans, the rest with monthly and final situation, within 45 days from the date of the invoice, with payment guarantee.

5. Deadline for starting works: 7 days after signing the contract and payment of the advance.

For further information, please contact us on the mobile phone: **00387 62 346 620 Mr Zdravko Crnković, and 00386 41 647 353 Mr Ivan Crnković.**

Prepared by:
Božica Đurković

Director:
Zdravko Crnković

Surčin 20.12.2022.

Društvo za geotehničko i inženjering i specijalne građevinske radove d.o.o. GEOINVEST ATZ Surčin